

Installation Data Manual





aps Packaged Pump Stations, underground tanks and stormwater attenuation tanks must be installed according to these instructions.

The local authority and the local region of the Environment Agency should also be consulted as to whether any particular code applies to installation. Failure to follow these installation instructions will make void our warranty and may result in tank failure.

Site access and conditions

It is the responsibility of the contractor to ensure suitable access to good hard ground that is safe and suitable for off-loading.

Wide/long loads

Where the tank is of such size that police/ private escort is required delivery times given are estimates only. In the event of delays outside our control eg. police re-routing or escort delays, the extra charges that result will be forwarded to the contractor.

Off-loading/handling

The contractor is responsible for offloading. Tank handling during off loading must be carried out with care to prevent rolling off the vehicle. Care must also be exercised to prevent accidental damage from impact or contact with sharp objects.

Tanks should be lifted using slings, not chains or wire ropes. Do not drag tanks along the ground for any distance and avoid jarring or bumps. Do not lift with water in the tank. (See page 1.2).

Note: Where transport height restrictions prevent the tank being loaded in the vertical position on the transport vehicle, the tank will be loaded at 45 degrees or as required to keep within the restrictions. In such cases it will be necessary for the tank to be off loaded onto a level area or well supported planks positioned adjacent to the 'lift' points and to support at least four ribs. The area must allow room to enable the tank to be rolled into the vertical position before lifting the tank into the excavation.

Set tank on smooth ground free of bricks and sharp objects. Chock/tie down to prevent movement in high winds. (See page

Tank dimensions

Dimensions given on drawings and literature shall be subject to manufacturing tolerances and should be checked physically prior to installation.

Installation procedures

The alternative methods of installation depend on the ground conditions, water table, the tank's location and whether the tank is fitted with feet or not. Installation should be carried out by a competent contractor in accordance with the above procedures, Health & Safety at Work legislation and good building practice. It is not possible to cover every condition in these instructions, therefore if in doubt contact us.

Tank specification

Check that you have received the correct specification tank. aps underground tanks are available in specifications to suit invert depths, concrete or pea gravel surround and ground water conditions; standard, heavy, extra heavy and special. (See pages 1.3 and 1.4).

For most applications the standard or heavy specifications are adequate. If the tank invert depth and/or water table depth is outside the range we shall be pleased to advise accordingly.

Siting aps septic tanks

British Standard BS 6297: 1983

recommends that sewage treatment works should be as far from habitable buildings as is economically practicable. The direction of the prevailing wind should be considered in relation to any properties when siting the

In accordance with the Building Regulations 2000. H2 2002 edition aps septic tanks should be sited at least 7m from any habitable parts of buildings, and preferably downslope.

The tank should not be installed near a road or driveway, where it could be subjected to high external loads, unless the installation is designed to withstand such loadings so they are not transferred to the tank shell.

Where the tank is to emptied using a tanker, it should be sited within 30m of a vehicle access provided that the invert level of the septic tank is no more than 3m below the level of the vehicle access. This distance

may need to be reduced where the depth to the invert of the tank is more than 3m. There should also be a clear route for the hose such that the tank can be emptied and cleaned without hazard to the building occupants and without the contents being taken through a dwelling or place of work.

Siting aps cesspools

aps cesspools should be sited at least 7m from any habitable building and preferably downslope. They should however be sited within 30m of a sludge removal tanker access and at such levels and position to operate and without hazard to the building

Extension access shafts

Check if extension shafts are required. These are available in 500mm high increments.

Note: Where coalescer units or pumps are incorporated that require guide rails, or ladders are fitted, the height of the extension access shaft/s should be measured accurately before ordering.

Health and safety


Installation should be carried out by a competent contractor in accordance with the above procedures, Health & safety at Work legislation and good building practice. A warning notice should be visible at the top of each access shaft - 'danger, harmful fumes' and 'respirators must be worn in this tank'. Before entering persons must be qualified in accordance with 'confined space' requirements.







Lifting and handling


- Do not roll or drop tanks. Only move tanks by lifting. Rolling tanks could damage fittings.
- · Tanks can be lifted using slings/ webbing straps as illustrated
- Where necessary a spreader bar should be used.
- · Guide the tank with guide lines.
- Never use chains or steel cables around tank shell.
- Do not drag tanks along ground for any distance.
- Avoid jarring or bumps.
- · Do not lift with liquid in the tank.
- Set tanks on smooth ground, free of rocks or other sharp objects.





Never drag along the ground or lift unevenly.







Storage

If tanks have to be stored temporarily prior to installation, they should be located:

- In an area where the chance of accidental damage or vandalism will be minimised.
- On a flat surface free from small or sharp objects.
- With efficient temporary anchorage to prevent high winds causing damage.






Tie down against high winds.






Specifications to suit invert depths and ground water conditions – pea gravel and concrete surrounds


Standard tanks




Heavy, extra heavy and special tanks




1800mm dia with pea gravel surround




2600mm dia with pea gravel surround



$1800 mm\, dia\, with\, concrete\, surround$



2600mm dia with concrete surround



Burial depths for 1200mm dia with concrete surround

Standard specification tanks

Maximum burial depth
to bottom of tank 4m

Maximum height of water
table above bottom of tank 1m


Heavy specification tanks

Maximum burial depth
to bottom of tank


Maximum height of water
table above bottom of tank

2m


3500mm dia with pea gravel surround




4000mm dia with pea gravel surround



3500mm dia with concrete surround



$4000 mm\, dia\, with\, concrete\, surround$









With concrete base and concrete/pea gravel surround


Installation with feet/chocks




Installation of APS Tankstor tank with



Installation without feet





Excavation details for concrete surround		1250/1200mm	1800mm	2600mm	3500mm	4000mm	
Max. burial depths (m) For your specific requirements refer to burial depth and water table depth charts on pages 3 and 4	Standard	dry excavation	4.0	4.0	5.0	5.7	6.2
	Heavy	dry excavation	6.0	5.6	6.0	7.25	7.3
		High water Table	-	3.0	3.75	5.0	5.2
	Extra Heavy	dry excavation	-	6.5	7.0	8.0	8.4
	Special	dry excavation	-	7.3	8.0	9.2	10.2
Minimum hardcore (mm), dependent on ground conditions		150	200	250	300	300	
Concrete base slab (mm) Slab thickness		100-150	150	220-240	240-300	250-300	
Concrete surround (mm), dependent on ground conditions		100-150	150	200-250	250-300	250-300	
Maximum Initial water fill depths, prior to backfilling (mm)			200	300	400	500	500
Tank internal diameter (mm)		1250/1200	1800	2600	3500	4000	
Tank external diameter (mm)		1300/1225	1875	2700	3650	4150	

For pea gravel surround see burial depth charts on pages 1.3 and 1.4.

Installation of tanks surrounded in concrete

Preliminary

Determine the size of the excavation from the dimensions of the tank and the incoming drain invert depth allowing for a minimum of 200-250mm (250-300mm for 1200mm and 1800mm did tanks) of concrete all round the tank. Where difficult ground conditions or the possibility of external loading exist, the concrete surround should be designed accordingly, ie. extra thickness and/or the use of reinforcing.

Excavation

Excavate allowing for easy placing of the tank and concrete and for consolidating concrete around the bottom half of the tank when backfilling.

Allowance should be made for any timbering or sheeting that may be required.

If the base of the excavation is of unstable ground - loose gravel, running sand, landfill type areas, peat, swamp or in clay areas subject to swelling/shrinking etc., excavate to allow for 250-300mm of hardcore and cover with a polythene membrane prior to placing concrete.

Procedure with feet/chocks

Feet and chocks can be provided during manufacture to enable the tank to be placed on a flat concrete base and levels checked prior to surrounding with concrete.

Feet are not load bearing and minimal water should be placed in the tank prior to placing backfill concrete.

- 1. Pour concrete base to correct depth and level off. Base to be reinforced as necessary.
- 2. When this concrete has set sufficiently, place the tank in position, check for levels including inlet/outlet inverts and fill with water in accordance with table on page 4.5. Ensure concrete slab is clean ready for placing concrete surround. Surround should preferably be placed within 48hrs of casting the base slab. Proceed to 3.


An alternative to feet for stabilising the tank are chocks. These are mounted each end of the tank to enable the tank to be maintained in a vertical position on a flat concrete slab.

The procedure is as follows.


- 3. Pour concrete base to correct depth and level off. Base to be reinforced as necessary. Work to full slab thickness see table on of page 1.5.
- 4. When this concrete has set sufficiently, place the tank in position and check for levels including inlet/outlet inverts. Also check the ribs are firmly seated on the concrete slab, or, at least every third rib. Those ribs standing free of the slab support with a tapered timber wedge (50mm widetapered 10°-15°). Where a number of ribs are unsupported place wedges from alternate sides.
- 5. Place backfill concrete (ST4 mix) up to the depth of the water in the tank ensuring the concrete is properly consolidated under the tank to prevent

- voids. Consolidate by hand Do not use vibrating pokers.
- 6. Continue by placing concrete around the tank at the same time filling with water to equalise pressure and resist floatation. Where the tank is divided into chambers ensure all chambers are filled equally.
- Connect up pipework, seat access shaft into socket and apply waterproof mastic/adhesive, or as applicable.
- 8. Top up the tank with water to inlet/ outlet invert level and place remainder of concrete to a depth of approximately 250mm above the top of the tank. Where extension access shafts are fitted, these can be surrounded in concrete once the main tank surround concrete has set. Important: Before surrounding circular or rectangular shafts with concrete, shutter internally to support the sides and safeguard against distortion.
- Where the concrete slab over the tank is to take vehicle loading, it should be reinforced in accordance with good practice to take the maximum load and should be extended onto unexcavated ground. It is important that vehicle loading is not transferred to the tank itself
- 10. Incorporate inspection cover frames in the normal manner.

Typical installation of APS tank without feet



Typical installation of APS tank with chocks & wedges







Installation of tanks surrounded in concrete


Procedure without feet

- 1. Place concrete along the centre of the excavation base and lower the tank into position 'puddling' it into the concrete to form cradle. Consolidate under the tank to prevent voids. Consolidate by hand - Do not use vibrating pokers.
- 2. Check the tank is truly vertical and level and that inlet/outlet invert levels are correct.
- 3. After the concrete has reached its initial set, fill with water in accordance with table on page 4.5.
- 4. Continue by placing concrete around

- the tank at the same time filling with water to equalise pressure and resist floatation. Where the tank is divided into chambers ensure all chambers are filled equally.
- 5. Connect up pipework, seat access shaft into socket and apply waterproof mastic/adhesive, or as applicable.
- 6. Top up the tank with water to inlet/ outlet invert level and place remainder of concrete to a depth of approximately 250mm above the top of the tank. Where extension access shafts are fitted, these can be surrounded in concrete once the main tank surround concrete has set. Important: Before
- surrounding circular or rectangular shafts with concrete, shutter internally to support the sides and safeguard against distortion.
- 7. Where the concrete slab over the tank is to take vehicle loading, it should be reinforced, in accordance with good practice, to take the maximum load. The reinforcing should be extended onto unexcavated ground. It is important that vehicle loading is not transferred to the tank itself.
- Incorporate inspection cover frames in the normal manner.


Cesspool tanks/ silage tanks etc.

When the concrete surround has fully cured, cesspool should be



Typical installation of APS tank without feet

Reinforced concrete slab designed to take vehicle loading



Venting aps septic tanks and cesspools

Adequate ventilation of the septic tank and the inlet pipework shall be provided to prevent the accumulation of fermentation gases.

Venting aps Separators

aps Separators should be vented in accordance with BS EN 752 (BS8301:1985 Building Drainage) or Health and Safety Guidance Notice HS (G) 41 for filling stations, subject to local authority requirements. In multiple chamber

separators, vent pipework must not be combined into a common stack below a point where pollutants contained could be transferred to other chambers.

aps Separator automatic alarm/ monitoring system

(Requirement of the Environment Agency's Pollution Prevention Guidelines PPG3) The aps automatic alarm/monitoring system provides continuous monitoring of the separator contents by sensing when the light liquid within the separator has filled to a predetermined level (with design

safety margins), and provides a simple audio-visual warning to alert the operator that the separator needs to be emptied. The system comprises 2 parts: a compact control unit and a probe unit. The control unit is installed in a nonhazardous area remote from the probe. It is self-contained and requires only a normal 240v AC electrical supply. The control incorporates a ATEX approved intrinsically safe circuit, which enables the probe unit to be used in Zone Zero Environments.

Installation of tanks surrounded with pea gravel backfill If you have an installation situation that is not covered by this installation booklet please contact our technical services department.

It is important that only properly trained and experienced contractors perform this method of installation.

Backfill material

Pea gravel or crushed rock is preferred as backfill material.

Clean and washed sand may be used. Sand must be compacted in 300mm lifts to above the tank top.

Requirements for backfill material are:

- · Clean and washed.
- Non-cohesive, inert material.
- Pea gravel or crushed rock.
- · Particle not larger than 20mm.
- Material free from rocks, ice, snow or organic material.

Excavating – general

Excavate allowing for easy placing of the tank and backfill and for consolidating backfill around the bottom half of the tank. Allowance should be made for any timbering or sheeting that may be required.

Filter fabric

Where there is a risk of the migration of pea gravel with the native soil, an approved filter fabric/geotextile is recommended.

Filling tanks

Do not fill tanks until backfill is to top of the tank. (Exception; Wet Hole see page 1.9). Where the tank is divided into chambers ensure all chambers are filled equally. Note: Where the chambers may require to be separated by load bearing partitions to accommodate different liquid levels the tank must be surrounded in concrete.

Depth of cover for standard and heavy specification tanks

No vehicle loads

1250/1200/1800/2600mm tanks are designed for a minimum cover of 600mm of backfill or 300mm plus 100mm reinforced concrete slab.

3500mm/4000mm 1100mm backfill or 900mm backfill plus 100-150mm reinforced concrete slab.

Vehicle loads


1250/1200/1800/2600mm tanks subjected to vehicle loading must have a minimum cover of 600mm of backfill plus a minimum 150mm reinforced concrete slab designed to take the maximum load without such loadings being transferred to the tank itself.

3500/4000mm as above but 1000mm backfill plus a minimum 150mm reinforced concrete slab as above.

The maximum depth of the cover is governed by the maximum drain invert depth and periodic high water table when encountered.

Depth of cover for extra heavy and special specification tanks, contact our technicalservices department.

Evacuation size, backfill and compaction







Installation of tanks surrounded with pea gravel backfill

Dry hole procedure

Excavation size - stable ground conditions Determine the size of the excavation from the dimensions of the tank and the incoming drain invert depth, allowing for a minimum of 450mm of backfill between the tank sides and the ends of the excavation. Excavation size – unstable ground conditions

Where the ground is unstable, eg. landfill type areas, peat, swamp or in clay areas subject to swelling/shrinking, the width of the backfill must be increased to a minimum of half the tank diameter between the tank sides and the ends of the excavation. If the base of the excavation is also of unstable ground, allow for 250-300mm of hardcore. After placing the hardcore, consolidate to ensure a firm base for the backfill.

- 1. Place a minimum of 150-300mm of approved backfill over the excavation bottom. Refer to table below.
- 2. Position tank carefully onto backfill bed and check for levels including inlet/ outlet inverts.
- 3. Place first 300mm lift of backfill evenly around the tank by shovelling and pushing beneath the tank bottom. between ribs and end domes to ensure complete support and to eliminate voids. (Where access is confined, long handled probes, curved to enable

reaching the underside of the tank, can be used). Place and compact further 300mm lifts as above to a minimum depth of 1/3rd tank diameter. The remainder of the backfill can be poured without consolidation except where required to support a cover slab.

- Connect up inlet, outlet and vent pipework, seat access shaft into socket and apply waterproof mastic/adhesive, or as applicable.
- Where a concrete slab is to be constructed over the tank to take vehicle loading, it should be reinforced in accordance with good practice to take the maximum load and should be extended onto unexcavated ground. It is important that vehicle loading is not transferred to the tank itself. Important: Before surrounding circular or rectangular shafts with backfill, shutter internally to support the sides and safeguard against distortion.
- Incorporate inspection cover frames in the normal manner

Wet hole procedure

Where there is water entering the excavation, the water level should be maintained below the foundation level by pumping with or without the aid of a pump well in one corner of the excavation.


If the water level cannot be lowered you will need to ballast the tank very carefully. Place the tank in the excavation adding only enough water ballast to sink it. The water level in the tank must never exceed the water level in the excavation. While adding ballast use only lifting strap to keep the tank in position. It is essential the backfill is distributed evenly round the base of the tank and thoroughly consolidated with the aid of long handled probes to eliminate any voids as set out in point 3 'Dry hole procedure'. To prevent flotation, mechanical anchoring may be required. See pages 1.11 and 1.12.

Backfill bed

Please refer to this table for the minimum amount of approved backfill to be used over the excavation bottom for your tank.

min backfill bed
150mm
150mm
200mm
250mm
300mm
300mm


2. Dry hole place backfill around tank




Wet hole backfill

3. Dry hole complete backfill

1. Dry hole backfill bed





option than bedding on pea gravel. **Excavation size**

This method of installation combines the

economy of pea gravel backfill and the

safety of a concrete cradle. For the less

experienced contractor this is a safer

Determine the size of the excavation from the dimensions of the tank and the incoming drain invert depth, allowing for a minimum of 200-250mm (ST4 mix) concrete and for a minimum of 450mm between the tank and the excavation.

Excavation size

Where the ground is unstable, eg. landfill type areas, peat, swamp or in clay areas subject to swelling/shrinking, the width of the backfill must be increased to a minimum of half the tank diameter between the tank sides and the ends of the excavation.


If the base of the excavation is also of unstable ground, allow for 250-300mm of hardcore. After placing the hardcore, consolidate and cover with a polythene membrane prior to placing concrete. Note: If mechanical anchoring is required, sinkers will need to be cast into the concrete cradle. See mechanical anchoring on page 1.11 and 1.12.

- 1. Place concrete along the centre of the excavation base and lower the tank into position 'puddling' it into the concrete to form cradle. Consolidate under the tank to prevent voids. Consolidate by hand – do not use vibrating pokers.
- 2. Check the tank is truly vertical, level and inlet/outlet invert levels are correct.
- 3. Place first 300mm lift of backfill evenly around the tank by shovelling and pushing around the tank sides, between ribs and end domes to ensure complete support and to eliminate voids. (Where access is confined long handled probes, curved to enable

- reaching the underside of the tank, can be used). After placing first lift of backfill the remainder of the backfill can be poured without further consolidation by hand.
- Connect up inlet, outlet and vent pipework, seat access shaft into socket and apply waterproof mastic/adhesive, or as applicable.
- 5. Where the concrete slab is to be constructed over the tank to take vehicle loading it should be reinforced in accordance with good practice to take the maximum load and should be extended onto unexcavated ground. It is important that vehicle loading is not transferred to the tank itself.
- 6. Incorporate inspection cover frames in the normal manner.

Note: Where the tank is divided into chambers ensure all chambers are filled equally. Where the chambers may require to be separated by load bearing partitions to accommodate different liquid levels the tank must be surrounded in concrete.

Pea gravel or other similar









APS mechanical anchoring system

Mechanical anchoring is required where the tank is to be surrounded in pea gravel and where water could enter into the excavation (underground water table, rainwater run-off etc.) or where the tank is to be surrounded in concrete and it is imperative the tank does not shift during the placement of this concrete. APS mechanical anchoring straps are available for all tanks. These are located over the designated ribs and held in position by locators positioned over the said ribs. Cables or straps should not be used between the ribs on the tank.

It is the responsibility of the tank owner or his technical representative to determine if mechanical anchoring is required for a specific installation.

If water could enter the excavation (underground water table, rainwater run-off etc.) we recommend the tank is mechanically anchored unless the minimum depth from tank top is, as in table on left.

The weight of over burden on top of the concrete anchor pad provides the anchoring force.

The pad is to prevent buoyancy but should be designed taking into account soil conditions eg. thickness and reinforcement. Anchor points should be spaced equal to the tank diameter plus 300mm on each side of the tank regardless of tank diameter. The anchor points must be aligned in accordance with the designated ribs plus or minus 25mm.

All anchor straps must be uniformly tightened with the ratchets. Straps should be a tight, snug fit to the ribs but must not cause the tank to deflect. It is recommended that the ratchets are positioned on alternate sides of the tank to ensure the tank remains vertical during tensioning.


Check the tanks internal diameter before and after tensioning the straps with a gauge rod to ensure against deflection.

Do not fill with product or water until backfill is level with top of tank except when backfilling with concrete.

When backfilling with concrete, we advise that the tank is filled with water to a corresponding level with the concrete to equalise pressure. Where the tank is divided into

chambers, ensure all chambers are filled equally. See installation procedure for surrounding in concrete.

Do not strap here



Straps must not be placed between the ribs or passed over from one side to the other as stress will be transferred to the weakest part of the tank wall. Unless the aps system is used and positioned correctly the 25 year warranty will be nullified.

Minimum Burial depth

The following table shows minmum burial depths when mechaical anchoring is not required

Dia (mm)	No cover slab (mm)	150mm cover slab (mm)		
1800	1200	1100		
2600	1500	1400		
3500	1800	1700		
4000	2100	2000		

Water table 1150 (3500mm dia) Webbing strap Ratchet & sinker Pea gravel surround 2475 (1800mm dia) 4750 (4000mm dia)

Procedure for 'anchoring' tanks down

- 1. Check contents of kit.Install the galvanised sinker into the precast pockets of the concrete base. These must line up with the ribs of the tank. The 'holding down' ribs are indicated on the tank by a 'strap' label.
- 2. Using the 'short' length of webbing, pass the loop of the webbing through the sinker bringing it back on itself, then pass the remaining webbing through the loop and pull tight. (Sketch 1).
- 3. Taking the ratchet, remove the bolt. Place the top loop of the 'short' length of webbing between the opening from
- where the bolt has been removed and replace the bolt. (Sketch 2). Note the arm of the ratchet should be facing outwards.
- 4. Attach the 'long' length of the webbing to the opposite galvanised sinker in a similar way to that described in Stage
- 5. Then throw the remaining length of webbing over the tank, making sure that the webbing is not twisted.
- Slide the GRP strap locators on to the 'long' length of webbing and position the locators as shown in the drawing (see previous page).
- 7. Taking the end of the 'long' length of webbing, thread it through the slot of the ratchet and tighten up using the ratchet arm to give required tension.
- 8. On completion the ratchet tensioners should be well wrapped in 'DENSO' or similar tape for long-term protection if the tank is surrounded in pea gravel or similar backfill.

Anchoring kit contents for 1800mm dia:


- Short length of webbing x 1
- Long length of webbing x 1
- Galvanised sinker x 2
- Ratchet x 1
- GRP strap locators x 3
- Anchoring kit contents for


Anchoring kit contents for 2600,3500 & 4000mm dia:

- Short length of webbing x 1
- Long length of webbing x 1 Galvanised sinker x 2
- Ratchet x 1
- GRP strap locators x 5


Galvanised sinker

Top of sinker should protrude 100-120mm above concrete slab.






Sketch 3











Where sandy, permeable ground is saturated with water, wellpoint dewatering is a technique that lowers the ground water level over a defined area. This is achieved by simultaneously pumping from a number of wellpoints inserted into the water table.

Without wellpoint dewatering the contractor would be trying to work or dig in ground that is virtually guicksand. The sides of the excavated hole would keep collapsing and any sand removed would be replaced by more sand running in, thus filling up the hole. This can result in danger to men, adjacent structures, roads, etc.

Once the wellpoints have been installed and the system has been running for some time, the contractor can then excavate in stable conditions.

As a general rule, any dewatering system must be kept running 24 hours a day because the water removed from the aground is replaced from the surrounding areas.



Two 170,000 litre APS Chambers being installed for the Port of Immingham


Using hydraulically operated modular bracing systems


Where excavations exceed 4m and extend to 22m or more, a proprietary bracing system, where little or no internal cross bracing is required, should be used.

Systems available comprise telescopic, hydraulic and rough adjustment walling modules connected to fixed length extension beams designed to provide support to interlocking sheet piling.

Where excavations are 20m or more in length a goal post arrangement is normally required to provide cross bracing support at the central point. This arrangement enables the aps tank to be passed under and into the excavation.








Top frame clear opening





To allow for the central goal post, the aps tank must be slung sufficiently offcentre to ensure clearance when finally positioning. Just sufficient angle of repose of the suspended aps tank can be achieved by using carefully calculated length slings.

Care must be exercised when the lower suspended end of the aps tank reaches the concrete base slab. It is recommended the first point of contact (end dome, first rib, etc) is protected. A vehicle tyre is effective in cushioning a load point.

Guide lines attached to the aps tank, fore and aft, are essential for guiding the tank into position and to help level the tank prior to final positioning on the base slab.

Up to 20m long excavations, temporary bracing can be provided by Mabey Hire Ltd. to provide a clear opening for installing the aps Tankstor or separator as illustrated.





Commissioning

Tanks, Site Pipework & Cable Ducts - Installation by contractor

The products supplied are generally installed by the customer or the appointed contractor which in the case of a package pumping station would include the underground and/ or above ground pipework, kiosk plinth and mounting the kiosk, underground cable ducts with drawstrings and conduit or cable trays for above ground cabling.

Installation instructions are supplied with every tank or chamber, Copies are available on request.

The cables supplied with the pump/s are normally 10m or 20m to special order. Any additional cabling required shall be supplied and fitted by the customer prior to the commissioning site visit.

Commissioning by special products division

APS Products, or their appointed contractor, will undertake the commissioning which comprises the placing of the pumps in the tank and pulling through the cable/s to the control panel, placing the control float switches in the tank and commissioning the system.

Commissions cost

The cost of commissioning is usually included in the overall price for the system. the benefit is that the cost is fixed for a period of six months. However, the full payment including the cost of commissioning has been undertaken or not. Where the commissioning cost is a separate charge, APS Products shall be entitled to revise the charge/s to cover any increases in the cost of labour and materials at the time of commissioning.

Site readiness for commissioning

Prior to arranging the date for commissioning the 'Site readiness for commissioning' form shall be completed and returned to APS Products to ensure the installation, power supply and other preparatory work required is completed. This is to ensure the commissioning visit is not aborted and extra charges for a return visit are not necessary.

One requirement is for water to be available in order to physically test the system for pumping operation, output and level controls.

Without the water or the media required to be pumped, the system can only be commissioned to theoretically operate. If after commissioning the system requires a further visit to adjust operation when the water or media is present, a further site visit charge will be applied.

Additional Charges

Breakdowns

After commissioning any further work required as a result of misuse, neglect, wilful damage, vandalism and blockages, shall be charged at current rates.

During installation & commissioningCharges will be raised for or in addition

Charges will be raised for or in addition to the agreed commissioning or service charge where:

- Site induction takes longer than 30 minutes
- Electricity supply is inadequate or fails
- Investigating as a result of a request to attend site but no fault found

- Visits to site where access is prevented by others, safety measures not in place or for other reasons beyond the control of APS Products
- Hours out of normal working hours will be charged according to the overtime rates applying
- Inability to undertake commissioning or servicing if dislodging or jetting is required prior to commencement.

Excluded in the commissioning/servicing:

- Overspill clear up
- Over pumping
- Cost arising out of a pollution incident

- Pipework or other leaks outside the pumping/valve chamber supplied
- Any internal damage that has occurred during installation by others.

Service Visits

After commissioning it is recommended a service of the pumps and specified associated equipment at intervals of approximately 12 months.

GRP vertical pump station

Installation of tanks surrounded in concrete

Determine the size of the excavation from the dimensions of the tank and the incoming drain invert depth allowing for a minimum of 200-250mm (250-300mm for 500/600 series tanks) of concrete all round the tank. Where difficult ground conditions or the possibility of external loading exist, the concrete surround should be designed accordingly, i.e. extra thickness and/or the use of reinforcing.

Excavate allowing for easy placing of the tank and concrete and for consolidating concrete around the bottom half of the tank when backfilling. Allowance should be made for any timbering or sheeting that may be required.

If the base of the excavation is of unstable ground – loose gravel, running sand, landfill type areas, peat, swamp or in clay areas subject to swelling/shrinking etc., excavate to allow for 250-300mm of hardcore and cover with a polythene membrane prior to placing concrete.

- Pour concrete base to correct depth and level off. Base to be reinforced as necessary.
- 2. When this concrete has set sufficiently, place the tank in position, check for levels including inlet/outlet inverts and fill with water in accordance with table

- below. Ensure concrete slab is clean ready for placing concrete surround. Surround should preferably be placed within 48hrs of casting the base slab.
- Place backfill concrete (ST4 mix) up to the depth of the water in the tank ensuring the concrete is properly consolidated under the tank to prevent voids. Consolidate by hand – do not using vibrating pokers.
- Continue by placing concrete around the tank at the same time filling with water to equalise pressure and resist floatation. Where the tank is divided into chambers ensure all chambers are filled equally.
- Connect up pipework, seat access shaft into socket and apply waterproof mastic/ adhesive, or as applicable.
- 6. Top up the tank with water to invert level and place remainder of concrete

- to a depth of approximately 250mm above the top of the tank. Where extension access shafts are fitted, these can be surrounded in concrete once the main tank surround concrete has set. Important: Before surrounding circular or rectangular shafts with concrete, shutter internally to support the sides and safeguard against distortion.
- 7. Where the concrete slab over the tank is to take vehicle loading, it should be reinforced in accordance with good practice to take the maximum load and should be extended onto unexcavated ground. It is important that vehicle loading is not transferred to the tank itself.
- 8. Incorporate inspection cover frames in the normal manner.

Excavation details (mm)	Series 100/200	Series 300	Series 400	Series 500	Series 600
Minimum hardcore thickness – dependent upon ground conditions	150	200	250	300	300
Concrete base slab thickness	150	150	220-240	240-300	250-300
Concrete surround – dependent upon ground conditions	100-150	150	200-250	250-300	250-300
Maximum initial water fill depths prior to backfilling	200	300	400	500	500
Tank internal diameters	1200	1800	2600	3500	4000
Tank external diameter including ribs	1225	1875	2700	3650	4150





Commissioning

For commissioning to be carried out, APS require that the questions below are answered satisfactorily. Please email **service@allpumpsolutions.com** for our Commissioning Request Form



The distance from control panel to bottom of pump station is (...m long) Please note: Standard pumps and floats have 10 m cables Additional cabling and junction boxes are the responsibility of the contractor, but can be supplied at extra cost. Please discuss prior to visit.



A water supply to commission the pumping station and for run testing the pump station is available.



Control panel mounted prior to attendance for commissioning and has electrical supply connected?



Access is available to the Control Panel - if applicable the Kiosk keys are available?



Has power been sized correctly? Normal earthing is acceptable i.e. no earth spikes are required.



Rising main (discharge pipework) and gravity lines are connected to the tank?



Guide brackets, galvanised steel guide rails and internal discharge pipes are fixed into tank?



Cable ducts with draw wires are in place between the control panel location and the tank?



Hardstanding area is installed around access shaft and vehicular access to Pumping Station is available?



Pumping Station is clear of debris, rubble, and silt so bottom of Chamber is visible? If applicable, Valve Chamber is clear of water?



Finished access opening size is correct to tank opening size to ensure pump can be installed correctly. Finished concrete slab opening should NOT be reduced in size to that of the tank opening otherwise pumps may not fit .



Shrewsbury | London | Sydney





